



- GENERAL NOTES**
- OUR SPECIFICATIONS DATED JANUARY 2020 APPLY TO THIS PROJECT.
 - THE WORKING WIDTH AVAILABLE TO THE CONTRACTOR TO CONSTRUCT THE NEW DRAINS SHALL CONSIST OF THOSE LANDS IMMEDIATELY ADJACENT TO THE DRAIN AND CONNECTIONS AND SHALL NOT EXCEED THE FOLLOWING AVERAGE WIDTHS:
 STA. 0+000 TO 0+894 - 20 METERS
 STA. 0+894 TO 0+967 - 10 METERS
 THE WORKING WIDTH FOR PURPOSES OF FUTURE MAINTENANCE SHALL BE 10M.
 - ALL OWNERS ALONG THE COURSE OF THE DRAIN SHALL MAKE AN ACCESS ROUTE FROM THE NEAREST ROAD TO THE DRAIN LOCATION AVAILABLE TO THE CONTRACTOR THE AVERAGE WIDTH OF THIS ROUTE SHALL NOT EXCEED 6 METERS. THE ACCESS ROUTE SHALL ALSO APPLY FOR FUTURE MAINTENANCE PURPOSES.
 - ALL UTILITIES TO BE LOCATED AND EXPOSED PRIOR TO CONSTRUCTION SO THAT THE NEW TILE GRADES CAN BE CONFIRMED. IF THERE IS A CONFLICT IN ELEVATION BETWEEN THE PROPOSED DRAIN AND THE UTILITY, THE ENGINEER IS TO BE NOTIFIED IMMEDIATELY.
 b) CONTRACTOR TO NOTIFY ALL UTILITIES 12 HOURS PRIOR TO HIS SCHEDULED TIME FOR STARTING THE ABOVE WORK.
 c) THE COST FOR THIS WORK SHALL BE INCLUDED IN THE ITEM ON THE EXTENT OF WORK AND NO EXTRA PAYMENT SHALL BE MADE TO THE CONTRACTOR, EXCEPT IF ROAD RESTORATION IS REQUIRED.
 - CONTRACTOR TO ARRANGE A PRE-CONSTRUCTION MEETING WITH THE ENGINEER, DRAINAGE SUPERINTENDENT, AND THE AFFECTED OWNERS. ALL PARTIES SHALL RECEIVE 48 HOURS NOTICE TO THE MEETING.
 - ALL CONCRETE AND PLASTIC TILE AND PIPE TO CONFORM TO 'SECTION C.1' IN THE SPECIFICATIONS.
 a) SEWER PIPE TO BE CONCRETE H. D. P. E. PLASTIC 312 MPA (BELL & SPIGOT WITH RUBBER GASKETS, CONFORMING TO C.S.A. 1026-08), PVC ULTRA RIB OR PVC SDR 35
 b) CONCRETE TILE SHALL BE HEAVY DUTY, UNLESS SPECIFIED AS 2000 D OR 2400 D ON PROFILE.
 - NEW TILE DRAINS TO BE LOCATED AS FOLLOWS:
 a) STA. 0+000 TO STA. 0+791 - ON SOUTH SIDE OF EXISTING 1971 DRAIN TILE.
 b) STA. 0+791 TO STA. 0+895 - IN SAME LOCATION AS EXIST. 300mm TILE (SEE DETAIL PLAN) EXIST. TILE TO BE DESTROYED AND EXPOSED TILE SHALL BE DISPOSED OF OFF-SITE.
 c) STA. 0+895 TO STA. 0+967 - NEW TILE TO BE LOCATED AS PER DETAIL PLAN
 d) EXISTING 1971 TILE FROM STA. 0+894 TO STA. 0+967 NOT DESTROYED IS TO BE ABANDONED FROM MUNICIPAL DRAIN STATUS
 e) EXISTING TILE DRAINS TO BE EXPOSED IN AS MANY LOCATIONS AS ARE NECESSARY TO CONFIRM THEIR EXACT LOCATION AND ELEVATION PRIOR TO CONSTRUCTION. EXACT LOCATION OF NEW TILE DRAINS THEN TO BE CONFIRMED BY DRAINAGE SUPERINTENDENT OR ENGINEER.

HODGINS DRAIN BRANCH "B" 2020
 TOWNSHIP OF LUCAN BIDDULPH

Drainage Superintendent:
ALEX VERBEEK
 519-672-4100

No.	REVISIONS	DATE

Drawn By: Rk4ak Field Book: GFS JOB No: 219164 Drawing No: 1 of 1
 Date: JULY 9, 2020

SPRIET ASSOCIATES LIMITED
 LONDON CONSULTING ENGINEERS
 155 YORK STREET - LONDON (519) 672-4100 - FAX 148